

Subdivisional Lines of T 4 N., R. 37 E., W.M.

Chains		Feet
	N. bet. Secs. 33 & 34 Var. 20° 30' E.	
40.00	Set fir post on level for $\frac{1}{4}$ Sec. Cor. A fir, 10 ins. diam. brs. S. 74° E., 19 lks. dist. A fir, 8 ins. diam. brs. N. 75° W., 14 lks. dist.	
65.50	Wagon Road to Weston, course E. and W., and cabin E. about 3 chs., Mason Deardorff's.	
80.00	Set fir post on N.W. slope for Cor. to Secs. 27, 28, 33 & 34. A fir, 20 ins. diam. brs. N. 12° E., 50 lks. dist. A fir, ins. diam. brs. S. 8° E., 32 lks. dist. A fir, 18 ins. diam. brs. S. 48° W., 30 lks. dist. A spruce, 14 ins. diam. brs. N. 12° W., 17 lks. dist.	
	Land; surface rolling Soil; 3rd and 2nd rate. Heavy timber, but much of it cut, fir, tamarack, spruce and hemlock. Yew, alder and willow underbrush	
	August 19th, 1879	
	E. on a random line bet. Secs. 27 & 34 Var. 21° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.62	Intersected N. & S. line, 32 lks. N. of Cor. to Secs. 26, 27, 34 & 35, from which Cor. I run N. 89° 46' W. on a true line bet. Secs. 27 & 34	
	Var. 20° 00' E.	
39.81	Set fir post in small open glade for $\frac{1}{4}$ Sec. Cor. on S.W. hillside. A fir, 13 ins. diam. brs. N. 34° E., 81 lks. dist. A fir, 24 ins. diam. brs. S. 46° W., 111 lks. dist.	
44.50	Brook, 4 lks. wide, course N.W.	
79.62	The Cor. to Sec. 27, 28, 33 & 34 Land; surface broken Soil; 3rd rate, Mostly heavy timber, tamarack, fir, spruce and hemlock.	