

## Subdivisional Lines of T 4 N R 37 E., W.M.

Chains	Feet
	<p>A fir, 12 ins. diam. brs. N. 30° E., 112 lks. dist.  A fir, 9 ins. diam. brs. S. 74° W., 120 lks. dist.  No other trees  Land; surface very broken and mountainous.  Soil; 3rd rate.  Some timber in places, but mostly open, fir, tamarack &amp; pine; good grass on open ground.</p>
	<p>N. bet. Secs. 9 &amp; 10  Var. 22° 45' E.</p>
11.00	Spring branch, course N.E.
28.00	On spur and begin steep descent
40.00	Set basalt stone, 13 x 10 x 6 on steep N.E. face of spur for $\frac{1}{4}$ Sec. Cor. A fir, 12 ins. diam. brs. S. 72° E., 128 lks. dist. A fir, 6 ins. diam. brs. S. 54° W., 86 lks. dist.
40.50	Steep precipice impossible to ch.; I set flag and cross The Walla Walla River to line, I measure a base S. of 50 lks. giving an angle of 7° whence Sine Co Sine lks. 1219 : : 9945 : : 50 : 408 making
44.08	Thence back to river, 100 to N. bank, 75 lks. wide, course N.W.
51.00	Thomas Chandler's house, brs. N. 42° W.
59.00	Sam's house, brs. S. 58° W.
64.00	Ravine, opens, S.W.
80.00	Set basalt stone, 18 x 8 x 6 on steep W. mountain side for Cor. to Secs. 3, 4, 9 & 10. Land; surface very broken and precipitous. Soil; 3rd rate. Large part worthless; small part 1st rate. on river bottom. Some timber on the hillside, Pine, Tamarack and Fir. Some grass; small part on river adapted to farming. August. 21st, 1879.
	E. on a random line along the S. Bdys. of Secs. 3, 2 & 1,