

Subdivisional Lines of T 4 N., R 37 E., W.M.

Chains		Feet
21.50	In gulch, course S.W.	
39.00	On spur, extending W.	
40.00	Set basalt stone on N. side of ridge for $\frac{1}{4}$ Sec. Cor.	
46.00	In gulch, opens W.	
66.50	Fence and field, course N.W. and S.E.	
76.40	Intersected 1st standard Parallel N. 14.60 chs. W. of standard Cor. to Secs. 34 & 35	
	Set fir post at point of intersection on S. slope in mound of stone in field, for Cor. to Secs. 2 & 3.	
	Land; surface, mountainous	
	Soil; 3rd and 2nd rate.	
	Good grass.	
	Some good farming land; about $\frac{2}{3}$ of Sec. 2 is well timbered.	
	At this standard Cor. the post was gone and but no witness tree left, the others were cut down.	
<hr/> N. bet. Secs. 3 & 4		
		Var. 22° 00' E.
	Across small spurs and ravines	
40.00	Set basalt stone, 16 x 12 x 4 on steep S. face of ridge for $\frac{1}{4}$ Sec. Cor.	
71.00	On ridge extending, E. & W.	
77.46	Set basalt stone, 14 x 10 x 5 on steep N. side, of ridge at intersection of 1st Standard Parallel N. for Cor. to Secs. 3 & 4. 1432 chs. W. of standard Cor. to Secs. 33 & 34, also set post in mound of stone.	
	Land; surface mountainous	
	Soil; 3rd rate. Good grass, valuable only for grazing.	
		August 23rd, 1879.
	Note:- after long and diligent search I could not find no trace of mounument for Standard Cor. to Secs. 33 & 34, which I therefore proceed to re-establish.	
0 v	<hr/> W. on a random line bet. Secs. 21 & 28	
		Var. 19° 15' E.