

## Subdivisional Lines of T. 4 N., R. 37 E., W.M.

Chains		Feet
82.30	<p>The cor. to Secs. 15, 16, 21 &amp; 22</p> <p>Land; surface, W. 65 chs. undulating; E 17, broken</p> <p>Soil; 2nd and 3rd rate.</p> <p>Timber was heavy once, but is nearly all cut, pine, fir, and tamarack.</p> <p>Dense undergrowth in places.</p>	
	<p>W. on a random line bet. Secs. 17 &amp; 20</p> <p style="text-align: right;">Var. 23° 00' E</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.60	<p>Intersected N. &amp; S. line, 420 lks. N. of Cor. to Secs. 17, 18, 19 &amp; 20, from which Cor. I run</p> <p>N. 87° E. on a true line bet. Secs. 17 and 20</p> <p style="text-align: right;">Var. 20° 00' E</p>	
21.00	Chouse Creek, 16 lks. wide, course N.	
40.30	Set basalt stone, 14 x 9 x 5 on steep S. hillside for $\frac{1}{4}$ Sec. Cor.	
74.00	Cross gulch, course S. 70°W.	
80.60	<p>The Cor. to Secs. 16, 17, 20 &amp; 21</p> <p>Land; surface very broken and mountainous</p> <p>Soil; 3rd rate.</p> <p>Some timber along creek and in gulch, fir, tamarack, pine and balm, good grass on open hillside.</p> <p>The post and three of the witness trees are still standing as described.</p>	
	<p>N. bet. Secs. 16 &amp; 17</p> <p style="text-align: right;">Var. 23° 00' E.</p>	
1.50	Spring branch, course S. 70° W.	
34.00	Fence and field, course E. & W.	
40.00	<p>Set basalt stone, 15 x 10 x 6 in field for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>A pine, 40 ins. diam. brs. E. 262 lks. dist.</p> <p>Wm. Petrie's house brs. S. 50° W., about 2 chs.</p> <p>Sylvester Glaspy's " S. 70° W., " 10 chs.</p>	
56.50	Fence and leave field, course E. & W.	