

Subdivisional lines of T 4 N R 37 E., W.M.

Chains		Feet
30.88	Intersected N. and S. line, 368 lks. S. of Cor. to Secs. 8, 9, 16 & 17, from which Cor. I run S. 87° 22' W. on a true line bet. Secs. 8 & 17 Var. 21° 45' E.	
2.50	Road to Walla Walla, course N.W. and S.E.	
32.00	Gulch, open, N.W.	
40.00	Set basalt stone, 20 x 14 x 5, on N. slope for $\frac{1}{4}$ Sec. Cor. A Pine, 10 ins. diam. brs. N. 76° E., 73 lks. dist. A Pine, 20 ins. diam. brs. S. 36° E., 143 lks. dist.	
30.88	The cor. to Secs. 7, 8, 17 & 18 Land; surface, E. $\frac{1}{2}$ mile rolling, W. $\frac{1}{2}$ broken Soil; 3rd and 2nd rate. A few scattering trees near $\frac{1}{2}$ mile cor. Good grass Some good farming land.	
	W. on a random line bet. Secs. 7 & 18 Var. 27° 00' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
83.94	Intersected W.Bdy. 327 lks. N. of Cor. to Secs. 7 & 18, from which cor. I run N. 87° 40' E. on a true line bet. Secs. 7 & 18 Var. 21° 00' E.	
5.00	James Isley's house, brs. S. 50° E. " " " " S.	
15.00	Leave field, course N.W. and S.E.	
43.94	Set basalt stone, 18 x 8 x 6 on E. brow of bluff for $\frac{1}{4}$ Sec. Cor.	
45.50	Begin steep descent	
76.50	Chaise Creek, course N.W.	
83.94	The cor. to Secs. 7, 8, 17 & 18 Land; surface, W. $\frac{1}{2}$ mile, undulating, E. $\frac{1}{2}$ mile, steep mountain sides Soil; W. $\frac{1}{2}$ mile, excellent, 2nd rate, E. $\frac{1}{2}$ 3rd rate. Some good timber in creek bottom, fir, pine, tamarack & balm.	