

Subdivisional Lines of T. 4 N., R. 37 E., W.M.

Chains	Feet
	<p>Good grass, good grazing land.</p> <p>There is a saw mill on N.E. <math>\frac{1}{4}</math> of Sec. 5 and some improvements on N.W. <math>\frac{1}{4}</math>. There is some 1st rate land in river bottom.</p> <p style="text-align: right;">Aug. 30th, 1879.</p>
	<hr/> <p>N. on the W. bdy. of Sec. 7.</p> <p style="text-align: right;">Var. 21° 00' E.</p>
72.00	Chouse Creek, 12 lks. wide, course N.W.
80.00	Set basalt stone, 16 x 10 x 5 and marked post in mound of stone, on steep S.W. hillside for Cor. to Secs. 1, 12, 6 & 7
	Aug. 30, 1879.
	<p>Note:- I built mounds of stone at Cors. instead of digging pits and making mounds of earth, because they are more easily found and remain more permanent than those made of earth.</p> <p>I have indicated as near as possible the lines of timber and prairie, it is difficult to do this as the timber is principally in gulches where the surface is very broken.</p>
	<hr/> <p>General Description</p> <hr/>
	<p>The surface of this township is all mountainous except a small part along the Walla Walla river, the Southern part a rolling Plateau, the Northern and N.Eastern the High and irregular bluffs. of the river. The S. part is well timbered and Secs. 1 &amp; 2 in the N. part. in the broken part the timber is in the gulches, opening to the N.; there is some good agricultural land on the plateaus and in river bottom. The Walla Walla River affords excellent water power, there is one sawmill on Sec. 5, There are about 20 settlers in the tp. It is valuable principally for timber.</p>