

## Subdivisional Lines of T. 4 N., R. 37 E., W.M.

Chains		Feet
44.40	Ravine, 50 ft. deep, course N. 80° W.	
45.35	Trail, brs. N. 10° W., and S. 10° E.	
	Enter scattering timber, brs. N.W. and S.E.	
60.00	Ridge point, 400 ft. above creek, brs. W.	
	Note:- I erect a flag at this point for a test sight from one of the high ridges visible to the N.	
	Descend through dense undergrowth, brs. E. and W. into deep ravine.	
64.00	Ravine, 200 ft. deep, course W.	
	Ascend along steep W. slope of mountain. Leave undergrowth	
80.00	Set a pine post, 4 ft. long, 6 ins. sq., 24 ins. in the ground, struck rock and raised a mound of stone around for Cor. of Secs. 13, 14, 23 & 24, marked	
	T 4 N., S 13 on N.E., R 37 E., S. 24 on S.E., S 23 on S.W. and S. 14 on N.W. faces,	
	with 3 notches on S. and 1 notch on E. edges, from which	
	A pine, 16 ins. diam. brs. N. 40° W., 2.97 chs. dist. marked T. 4 N., R. 37 E., S. 14 B.T.	
	No other trees in limits, raised mound of stone, 2 ft. base, 1½ ft. high W. of Cor., post impracticable.	
	Land; mountainous.	
	Soil; gravel and rock; 4th rate.	
	Timber; fir, tamarack, pine, alder, spruce and wild cherry.	
	Undergrowth, Mountain laurel, small fir and huckleberry.	
	Mountain lands, 80.00 chs.	
	N. 89° 52' E. on a random line bet. Secs. 13 & 24	
40.00	Set temp. ¼ Sec. Cor.	
80.36	Intersect E. Bdy. of the Tp. 14 lks. S. of the Cor. of Sec.	
	3, 18, 19 and 24, which is a stone, 4 x 10 x 8 ins.	
	above ground, marked and witnessed as described by the surveyor general, thence I run	
	S. 89° 46' W. on a true line bet. Secs. 13 & 24	
	Descend steep S.W. mountain side.	
30.25	Enter scattering timber, brs. N. and S.	