

Subdivisional Lines of T. 4 N., R. 37 E., W.M.

Chains		Feet
	scattering timber.	
81.60	Intersect N. and S. line, 97 lks. S. of the Cor. of Secs. 14, 15, 22 & 23, described heretofore at point of intersection, set a pine post, 6 ins. sq., 3½ ft. long; 2½ ft. in the ground for Closing Cor. of Secs. 14 and 23, marked C.C. T 4 N R 37 E on E. S 23 on S. and S 14 on the N. Faces, with 2 grooves on the E. and 3 grooves on the S. faces, from which A pine, 48 ins. diam. brs. N. 16° 30' E., 25 lks. dist. marked, T 4 N R 37 E S 14 B.T. A pine, 16 ins. diam. brs. S. 68° E., 92 lks. dist. marked T. 4 N R 37 E, S 23 B.T. I destroy all marks on the old Cor. pertaining to the survey E. Land; mountainous Soil; gravelly loam and stony, 2nd and 4th rate. Timber; tamarack, fir, pine and alder. Undergrowth, mountain laurel, huckleberry and small firs. Mountainous land. 81.60 chs. June 15, 1902	
	From the old Cor. of Secs. 15 & 22, I run N. 0° 02' W. bet. Secs. 14 & 15 Ascend gradually along E. slope through scattering timber.	
6.25	Ridge point, brs. N.E. S.W. Descend through heavy fir and tamarack timber, brs. N.E. and S.W.	
17.25	Foot of ravine, 200 ft. deep, course N. 60° E. Ascend gradually along E. slope of spur.	
19.00	Leave timber, brs. N.E. and S.W.	
40.00	Set an ironstone, 20 x 15 x 6 ins. 10 ins. in the ground, struck rock, raised mound of stone around for ¼ Sec. Cor. marked ¼ on the W. face, raised mound of stone, 3 ft. base, 2 ft. high W. of Cor. Pits impracticable.	
42.00	Ridge point, brs. N.E. and S.W. Descend.	