

## Exterior Bdy. of T. 4 N., R. 38 E., W.M. (N. Bdy.)

Chains		Feet
	<p>face of ridge for Cor. to Secs. 32 &amp; 33.</p> <p>A Pine, 10 ins. diam. brs. N. 84° E., 330 lks. dist.</p> <p>A Pine, 30 ins. diam. brs. N. 82° W., 450 lks. dist.</p> <p>Land; surface, very broken by deep gulches and prominent spurs.</p> <p>Soil; third rate.</p> <p>Scattering Pine and Fir timber.</p>	
	<hr/> <p>E. on the S. Bdy. of Sec. 33</p> <p style="text-align: right;">Var. 22° 15' E.</p>	
2.25	Spring branch, course S.W.	
32.00	Spur, extending S.W.	
38.00	On high rocky spur, ex. S.W.	
40.00	Set basalt stone, 17 x 12 x 4 on E. face of spur, for $\frac{1}{4}$ Sec. Cor.	
	<p>A Pine, 36 ins. diam. brs. N. 18° W., 223 lks. dist.</p> <p>No other tree.</p>	
51.00	In gulch, opens S.W.	
64.75	On spur, extend S.	
78.75	" " " "	
80.00	Set basalt stone, 14 x 10 x 5 on steep E. side of spur for Cor. to Secs. 33 & 34, from which	
	<p>A fir, 12 ins. diam. brs. N., 76° E., 104 lks. dist.</p> <p>A fir, 18 ins. diam. brs. N. 22° W., 134 lks. dist.</p> <p>Land; surface broken by spurs and gulches, extending S.</p> <p>Soil; 3rd rate and worthless, very rocky</p> <p>Scattering Pine and Fir timber.</p> <p style="text-align: right;">June 3rd, 1879.</p>	
	<hr/> <p>E. on the S. Bdy. of Sec. 34</p> <p style="text-align: right;">Var. 16° E.</p>	
	Steep and rocky descent	
21.50	Spring branch, course S.	
36.50	Spring branch, course S.W.	
40.00	A fir tree, 12 ins. diam. on N.W. side of spur for $\frac{1}{4}$ Sec. Cor.	