

Exterior Bdy. of T. 4 N., R. 38 E., W.M. (N. Bdy.)

Chains		Feet
	<p>A fir, 15 ins. diam. brs. S. 6° E., 36 lks. dist. No tree on N. side</p>	
53.00	On spur, extending S.W.	
76.00	Spring branch, cours S.E.	
77.00	Spring branch, cours S.W.	
80.00	Set basalt stone on S.W. face of spur in mound of stone for Cor. to Secs. 34 & 35. Set stake in mound of stone in lieu of pits. No green trees, timber all dead. Land; surface mountainous Soil; 3rd rate and worthless Some scattering fir and pine timber.	
E. on the S. Bdy. of Sec. 35		
		Var. 22° 45' E.
10.00	On spur, extending N. and S.	
40.00	Set fir post on N.E. face of spur for $\frac{1}{4}$ Sec. Cor. A tamarack, 15 ins. diam. brs. N. 25 lks. dist. A fir, 5 ins. diam. brs. S. 6° E., 31 lks. dist.	
68.50	Creek, 25 lks. wide, course S.	
80.00	Set basalt stone, 20 x 10 x 4 on W. face of spur for Cor. to Secs. 35 & 36, from which A Pine, 10 ins. diam. brs. N. 28° E., 17 lks. dist. A Pine, 6 ins. diam. brs. N. 31° W., 11 lks. dist. Land; surface very broken and mountainous. Soil; 3rd rate and worthless. Some good timber, pine, fir, and tamarack, but mostly scattering.	
E. on the S. Bdy. of Sec. 36		
		Var. 19° 45' E.
	Along irregular S. slope of mountain ridge.	
40.00	Set basalt stone, 18 x 10 x 5 on S. face of spur for $\frac{1}{4}$ Sec. Cor. A fir, 16 ins. diam. brs. N. 46° W., 38 lks. dist. No trees on S. side.	
55.75	An impassible canyon. I sent flag on E. side of canyon and	