

Subdivisional Lines of T 4 N R 38 E., W.M.

| Chains | | Feet |
|--------|--|------|
| 81.62 | Intersect the W. Bdy. of the T. 19 lks. N. of the Cor. of Secs. 1, 6, 7 & 12, heretofore described, thence I run S. 89° 47' W. on a true line bet. Secs. 1 & 12, along N. slope, over low spurs and shallow ravines through scattering timber and dense undergrowth. | |
| 3.80 | A spring branch, 2 lks. wide, course N. 10° E. Thence ascend | |
| 25.00 | Top of spur, 100 ft. high, extending N. Begin descent. | |
| 41.62 | Set a basalt stone, 15 x 8 x 6 ins., 10 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; from which A fir, 8 ins. diam. brs. S. 5° W., 1 lks. dist., marked $\frac{1}{4}$ S 112 B T A fir, 18 ins. diam. brs. N. 55° W., 33 lks. dist., marked $\frac{1}{4}$ S 1 B T | |
| 52.60 | A dry ravine, 75 ft. deep, course N. Thence ascend | |
| 64.00 | Top of spur, 75 ft. high, extending N. Descend | |
| 78.60 | A branch, 5 lks. wide, course N. 10° W. Thence ascend | |
| 81.62 | The Cor. of Secs. 1, 2, 11 & 12 Land; mountainous Soil; 1st and 2nd rates Timber; fir, pine, spruce Undergrowth; willow, maple and wild berry Mountainous or heavily timbered land or land covered with dense undergrowth and exceptionally difficult to survey. 81.62 Chs. | |
| <hr/> | | |
| | From the Cor. of Secs. 14, 15, 22 & 23 I run N. 0° 1' W. bet. Secs. 14 & 15. Ascend S. slope over precipitous ground, through dense undergrowth. | |
| 4.50 | Top of spur, 25 ft. above Sec. Cor. Extend W. Thence descend along N.W. slope | |
| 39.50 | Top of spur, 100 ft. high, extends N. 50° W., thence descend. | |
| 40.00 | Set a basalt stone, 15 x 8 x 8 ins., 10 ins. in the ground | |