

Subdivisional Lines of T 4 N R 38 E W. M.

Chains		Feet
	From the Cor. of Secs. 19, 20, 29 & 30, heretofore described, I run	
	N. 0° 1' W. bet. Secs. 19, 20.	
	Gentle ascent through heavy timber and dense undergrowth	
40.00	Set a fir post, 3 ft. long, 3 ins. sq., 24 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S 19 on W. and 20 on E. face; from which	
	A fir, 18 ins. diam. brs. N. 85° E., 13 lks. dist. marked $\frac{1}{4}$ S 20 B T	
	A fir, 16 ins. diam. brs. W. 19 lks. dist. marked $\frac{1}{4}$ S 19 B T	
41.72	Settlers' road brs. N. 70° E. and S 70° W.	
59.00	Settlers' road brs. N. 50° E., S. 50° W.	
80.00	Set a basalt stone, 12 x 5 x 6 ins., 8 ins. in the ground for Cor. of Secs. 19 & 20, marked with 5 notches on E. and 3 notches on S. edge; from which	
	A fir, 16 ins. diam. brs. S. 27° E., 36 lks. dist. marked T 4 N R 38 E S 20 B T	
	A fir, 16 ins. diam. brs. S. 42° W., 56 lks. dist. marked T 4 N R 38 E S 19 B T	
	Land; mountainous	
	Soil; 1st and 2nd rates	
	Timber, fir, pine, spruce	
	Undergrowth, willow, maple and wild berry	
	Mountainous or heavily timbered land or land covered with dense undergrowth and exceptionally difficult to survey,	
	80.00 Chs. July 27, 1905:	
	<hr/>	
	Thence I run	
	S. 89° 47' E. on a random line bet. Secs. 17 & 20	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.10	Intersect the N. and S. line, 19 lks. N. of the Cor. of Secs. 20 & 21	
	Thence I run	
	N. 89° 39' W. on a true line bet. Secs. 17 & 20. Descend over precipitous ground through dense undergrowth.	