

## Subdivisional Lines of T 4 N R 38 E., W.M.

Chains		Feet
10.00	<p>Ft. of descent, 75 ft. below Sec. Cor.  A spring branch, 5 lks. wide, brs. N.E.  Thence ascend over precipitous E. slope through scattering timber and dense undergrowth.</p>	
40.05	<p>The point for <math>\frac{1}{4}</math> Sec. Cor. falls on sliding rock, where it is impossible to set the Cor. and secure its safety.  Therefore, I continue to  (See pg. 83 of Supplemental Field Notes T 4 N R 38 E)  Ascent through heavy timber and scattering undergrowth.</p>	
80.10	<p>The Cor. of Secs. 19 &amp; 20  Land; mountainous  Soil; 1st and 2nd rates  Timber; fir, pine, spruce  Undergrowth; willow, maple and wild berry  Mountainous or heavily timbered land or land covered with dense undergrowth and exceptionally difficult to survey,  80.10 Chs.</p>	
	<hr/> <p>W. on a random line bet. Secs. 18 &amp; 19</p>	
40.00	<p>Set temp. <math>\frac{1}{4}</math> Sec. Cor.</p>	
77.75	<p>Intersect the W. Bdy. of the T 44 lks. N. of the Cor. of Secs. 13, 18, 19 &amp; 24.  Thence I run  N. 89° 41' E. on a true line bet. Secs. 18 &amp; 19.  Ascend precipitous ground through dense undergrowth.  (See pg. Supplemental Field Notes, T 4 N R 38 E.,)</p>	
39.50	<p>Enter scattering green timber, brs. N. and S.</p>	
69.00	<p>Top of ascent, 500 ft. above Sec. Cor.  Thence over rolling ground through heavy timber and dense undergrowth.</p>	
69.75	<p>Edward's cabin brs. S. about 5.00 Chs. dist.</p>	
78.29	<p>Cor. of Secs. 19 &amp; 20  Land; mountainous  Soil; 1st and 2nd rates.  Timber; fir, pine, spruce  Undergrowth, willow, maple and wild berry</p>	