

Dependent Resurvey of Part of S. Bdy. of T 4 N R 38 E.

Chains	Feet
	marks grown over. (Old B.T.)
	A pine, 12 ins. diam., bears S. 12° W., 35 lks. dist. marked $\frac{1}{4}$ S B T. Obliterate marks. (Old B. T.)
	A fir, 18 ins. diam., brs. N. 30° W., 69 lks. dist. marked $\frac{1}{4}$ S 35 B T. (New B.T.)
	The georgaphic position of this corner is latitude 45° 46 $\frac{1}{2}$ ' N., and longitude 118° 02' W.
	Thence N. 89° 21' W., on true line along the S. bdy. of Sec. 35.
2.65	Desc. 140 ft. over S.W. slope, through heavy timber and dense undergrowth. The closing cor. of secs. 2 and 3, which is a basalt stone, 18 x 8 x 7 ins., firmly set, marked with 2 grooves on E., 6 grooves on S., and 4 grooves on W. face.
	At point for cor.
	Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with the original stone deposited at the base, for closing cor. of secs. 2 & 3, with brass cap marked
	T4NR38E S35 S 3 S 2 T3N R38E C C 1939
	from which
	A pine, 12 ins. diam., bears S. 13° W., 80 lks. dist., marks grown over. (Old B.T.)
	A fir, 18 ins. diam. brs. S. 76° E., 40 lks. dist., marked T 3 N R 38 E S 2 C C B T. (New B.T.)
	Desc. 280 ft. over SW. slope.
12.10	Creek, 4 lks. wide, course S. 10° E., asc. 608 ft. over E. slope.
31.10	Spur, slopes S.E.; desc. 99 ft. over S.W. slope.
39.42	Proportionate measurement.
	Set an iron post, 3 ft. long, 2 ins. diam., 12 ins. in the ground to bedrock, and in a mound of stone to top, for cor. of secs. 34 & 35 only, with brass cap marked
	T4NR38E S34 S35 T3NR38E S 3 1939
	from which
	A pine, 28 ins. diam., brs. N. 24° E., 200 lks. dist., marked T 4 N R 38 E S 35 B T.
	A fir, 30 ins. diam. brs. N. 7° W., 236 lks. dist. marked T 4 N R 38 E S 34 B T
	Land; mountainous Soil, rocky loam; 3rd rate. Timber, fir, pine, spruce, and tamarack. Undergrowth, alder, willow, huckleberry, vinemaple, and buckbrush.