

## Dependent Resurvey of Part of S. Bdy. of T 4 N., R. 38 E.

Chains		Feet
	N. 89° 21' W., along the S. Bdy. of Sec. 34.	
	Desc. 207 ft. over SW. slope, through heavy timber and dense undergrowth.	
7.45	Draw, course S.; asc. 52 ft. over SE. slope.	
12.50	Spur, slopes S. 20° E.; desc. 136 ft. over SW. slope.	
18.95	Draw, course S.; asc. 52 ft. over SE. slope	
23.35	Spur, slopes S. 20° E.; descend 171 ft. over SW. slope.	
32.15	Lookingglass Creek, 7 lks. wide, course S. 70° E.; asc. 50 ft. over NE. slope.	
39.25	Spring branch, 1 lks. wide, course N; along N. slope.	
39.42	The $\frac{1}{4}$ Sec. Cor. of Sec. 34 only, which is a basalt stone, 18 x 12 x 8 ins., firmly set, marked $\frac{1}{4}$ on N. face.	
	At point for Cor.	
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the original stone deposited at the base, for $\frac{1}{4}$ Sec. Cor. of Sec. 34 only, with brass cap marked	
	<u><math>\frac{1}{4}</math> S 34</u>	
	1939	
	from which	
	A fir, stump, 8 ins. diam., brs. N. 52° E., 43 lks. dist., marks rotted off. (Old B.T.)	
	A spruce, 40 ins. diam., brs. S. 79° W., 64 lks. dist., marked $\frac{1}{4}$ S B T. Obliterate marks. (Old B.T.)	
	A fir, 24 ins. diam., brs. N. 32° E., 46 lks. dist., marked $\frac{1}{4}$ S 34 B T. (New B.T.)	
	A fir, 18 ins. diam., brs. N. 51° W., 25 lks. dist., marked $\frac{1}{4}$ S 34 B T (New B.T.)	
	Thence	
	S. 89° 10' W., continuing measurements.	
	Along N. slope.	
42.87	New point for closing cor. of secs. 3 & 4, hereinafter described.	
47.00	Desc. 13 ft. over NW. slope.	
54.00	Lookingglass Creek, 7 lks. wide, course N. 80° E., asc. 20 ft. over gradual SE. slope.	
65.30	Lookingglass Creek, 7 lks. wide, course S. 70° E.; asc. 258 ft. over NE. slope.	
79.57	The cor. of Secs. 33 & 34 only, which is a basalt stone, 14 x 10 x 8 ins., firmly set, marked with 3 notches on E. and W. edges.	
	At point for Cor.	
	Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with the original stone deposited at the base, for cor. of secs. 33 & 34 only, with brass cap marked	