

Dependent Resurvey of Part of Subdivision of T. 4 N., R 38 E.

Chains	1883 and sec. 19 executed by Robert F. Omeg, Deputy Surveyor in 1905."	Feet
	I commence the dependent resurvey of the subdivisions at the cor. of secs. 34 & 35, on the S. bdy. of the Tp., heretofore described.	
	Thence	
	N. 0° 13' E., on true line bet. Secs. 34 & 35.	
	Asc. 414 ft. over SW. slope, through scattering timber and undergrowth.	
18.00	Spur, slopes SE.; desc. 20 ft. over rolling NE. slope.	
29.75	Dim dirt road, bears NW. and SE.	
40.17	The $\frac{1}{4}$ Sec. Cor., which is a basalt stone, 12 x 10 x 6 ins., firmly set, marked $\frac{1}{4}$ on W. face.	
	At point for cor.	
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the original stone deposited at the base, for $\frac{1}{4}$ Sec. Cor., with brass cap marked	
	$\begin{array}{c} \uparrow \\ \text{S34} \mid \text{S35} \\ \text{1939} \end{array}$	
	from which	
	A fir, 32 ins. diam., brs. S. 65° E., 12 lks. dist., marks grown over. (Old B.T.)	
	A fir, 30 ins. diam., brs. S. 87 $\frac{1}{2}$ ° W., 85 lks. dist., marks grown over. (Old B.T.)	
	Thence	
	N. 0° 09' E., continuing measurements.	
	Desc. 43 ft. over NE. slope.	
48.85	Draw, course E.; asc. 51 ft. over SE. slope.	
61.20	Spur, slopes E.; desc. 23 ft. over NE. slope.	
68.55	Draw, course E.; asc. 65 ft. over gradual SE. slope.	
77.45	Dim dirt road, brs. N.E. and S.W.	
80.47	The Cor. of Secs. 26, 27, 34 & 35, which is a basalt stone, 12 x 12 x 10 ins., firmly set in a mound of stone, marked with 2 notches on E. and 1 notch on S. edge.	
	At point for cor.	
	Set an iron post, 3 ft. long, 2 ins. diam., 12 ins. in the ground to bedrock, with the original stone deposited at the base, and in a mound of stone to top, for cor. of secs. 26, 27, 34 & 35, with brass cap marked	
	$\begin{array}{c} \text{T4NR38E} \\ \text{S27} \mid \text{S26} \\ \text{S34} \mid \text{S35} \\ \text{1939} \end{array}$	
	from which	
	A pine, 24 ins. diam., brs. N. 18° E., 84 lks. dist.,	