

## Dependent Resurvey of Part of Subdivisions of T 4 N., R 38 E.,

Chains		Feet
	T4NR38E S28 S27 S33 S34 1939	
	from which	
	A dead and fallen spruce, 14 ins. diam., brs. S. 74° W. 28 lks. dist., bearing traces of incomplete scribe marks. (Old B.T.)	
	A pine, 8 ins. diam., bears N. 42½° E., 40 lks. dist., marked T 4 N R 38 E S 27 B T. (New B.T.)	
	A pine, 8 ins. diam., brs. S. 28½° E., 38 lks. dist., marked T 4 N R 38 E S 34 B T. (New B.T.)	
	A pine, 12 ins. diam. brs. S. 55½° W., 46 lks. dist., marked T 4 N R 38 E S 33 B T. (New B.T.)	
	A pine, 9 ins. diam., brs. N. 35½° W., 59 lks. dist., marked T 4 N R 38 E S 28 B T. (New B.T.)	
	Land; rolling and mountainous Soil; sandy and rocky loam; 2nd and 3rd rate. Timber, fir, pine, spruce, and tamarack. Undergrowth, alder, willow, vinemaple, huckleberry, and Oregon grape.	
	From the cor. of secs. 26, 27, 34 & 35, heretofore describ- ed.	
	N. 89° 53' W., bet. Secs. 27 & 34.	
	Asc. 10 ft. over E. slope, through scattering timber and undergrowth.	
2.60	Flat topped ridge, brs. N. and S.; desc. 478 ft. over W. slope.	
8.45	Skyline road, brs. N. and S.	
15.00	Enter heavy timber and dense undergrowth, brs. N. and S.	
38.25	Dim dirt road, brs. N. and S.	
40.09	The ¼ Sec. Cor., which is a post, 3 ins. sq., 36 ins. long, firmly set, marked ¼ on N. side.	
	At point for cor.	
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the marked stake deposited at the base, for ¼ sec. cor., with brass cap marked	
	S 27 S 34	
	1939	
	from which	
	A fir snag, 12 ins. diam., brs. N. 33° W., 30 lks. dist., marked ¼ S B T. (Old B.T.)	
	A fir, 24 ins. diam., brs. N. 66° W., 54 lks. dist., marked ¼ S 27 B T. (New B.T.)	
	A spruce, 20 ins. diam., brs. S. 21° E., 72 lks. dist., marked ¼ S 34 B T. (New B.T.)	