


Dependent Resurvey of Part of Subdivisions of T 4 N R 38 E.,

Chains		Feet
	Over rolling land.	
42.30	McIntyre Lookout Road, brs. N. 30° W. and S. 30° E.	
48.00	Flat topped ridge, brs. N. and S.; desc. 113 ft. over E. slope.	
78.46	The cor. of secs. 19, 20, 29, and 30, heretofore described. Land; mountainous and rolling. Soil; sandy and rocky loam; 2nd and 3rd rate. Timber, fir, pine, spruce, and tamarack. Undergrowth, alder, willow, vinemaple, and huckleberry.	
	N. 0° 14' E., bet. Secs. 19 & 20. Asc. 17 ft. over SE. slope, through heavy timber and dense undergrowth.	
1.30	Dirt road, brs. NW. and SE.	
10.00	Top of ascent, brs. E. and W.; desc. 59 ft. over N. slope.	
32.85	Draw, course S. 70° E.; asc. 53 ft. over SE. slope.	
39.86	The $\frac{1}{4}$ sec. cor., which is the rotten remains of old stake, bearing traces of incomplete scribe marks. At point for cor. Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the marked stake deposited at the base, for $\frac{1}{4}$ sec. cor., with brass cap marked	
		
	from which	
	A fir, 26 ins. diam., brs. N. 85° E., 13 lks. dist., marks grown over. (Old B.T.)	
	A double fir, 40 ins. diam., brs. W., 19 lks. dist., marks grown over. (Old B.T.)	
	Thence	
	N. 0° 18' W., continuing measurements.	
	Asc. 21 ft. over SE. slope.	
41.85	McIntyre Lookout Road, brs. NE. and SW.	
79.62	The cor. of secs. 19 & 20, which is the broken remains of old basalt stone, with 5 notches on one piece and 3 notches on another piece. At point for cor. Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with the broken pieces of original stone deposited at base, for cor. of secs. 19 & 20 only, with brass cap marked	