

Exterior Lines of T. 4 S., R 29 E.

Chains		Feet.
	<p>marked T. 4 S., R. 29 E., S. 13 B.T.</p> <p>A Pine 14 ins. diam. brs. N. 28° W. 43 lks. dist., marked T. 4 S., R. 29 E., S. 12 B.T.</p> <p>Descent about 80 ft.</p> <p>Land; surface broken.</p> <p>Soil; 2nd and 3rd rate, heavily covered with Pine, Tamarack and Fir timber with much dense undergrowth of Pine, Tamarack and Fir.</p>	
	<hr/> <p>N. bet. Secs. 7 and 12.</p> <p style="text-align: right;">Var. 20° 30' E.</p>	
25.50	A brook 8 lks. wide, course N.E., ascent about 80 ft.	
35.00	Alvina Lowrie's house brs. E. about 6.00chs. dist.	
40.00	Set a post 4 ft. long 4 ins. diam. 2 ft. in ground for $\frac{1}{4}$ Sec. Cor., on slight E. slope for $\frac{1}{4}$ Sec. Cor., S. on W. face, from which,	
	<p>A Pine 20 ins. diam. brs. N. 67° E. 24 lks. dist., marked $\frac{1}{4}$ S.B.T.</p> <p>A Pine 14 ins. diam. brs. S. 48° W. 27 lks. dist., marked $\frac{1}{4}$ S.B.T.</p>	
54.50	Wagon road to Lowrie's place, course N.W. and S.E.	
67.00	A brook 12 lks. wide, course N.W.	
	Descent about 100 ft.	
72.00	Steep ascent to bench	
80.00	Set a basalt stone 18 x 10 x 5 ins. in mound of stone on rocky point W. slope for Cor to Secs. 1, 6, 7 and 12, marked with 5 notches on S. and 1 notch on N. edges, from which,	
	<p>A Pine 24 ins. diam. brs. N. 44° E. 48 lks. dist., marked T. 4 S., R. 30 E., S. 6 B.T.</p> <p>A Pine 22 ins. diam. brs. N. 33° W. 207 lks. dist., marked T. 4 S., R. 29 E., S. 1 B.T.</p>	
	No trees S., mound of stone around Cor. instead,	
	Ascent about 100 ft.	
	Land; surface rolling,	
	Soil; 2nd and small part 1st rate. Heavily covered with	