

## Exterior Lines of T. 4 S., R. 30 E., W.M.

Chains		Feet
	<p>marked T. 5 S., R. 30 E., S. 3 B.T.</p> <p>A Pine 20 ins. diam. brs. N. 50° W. 126 lks. dist.</p> <p>marked T. 4 S., R. 30 E., S. 34 B.T.</p> <p>Land; surface undulating,</p> <p>Soil; 3rd and 2nd rate; mostly scattering open Pine, Tamarack and Fir timber with open glades.</p>	
	<p>S. 89° 51' E. on a true line along the S. Bdy of Sec. 35.</p> <p style="text-align: right;">Var. 21° 45' E.</p> <p>Undulating,</p>	
40.00	<p>Set a basalt stone 18 x 12 x 5 ins. 12 ins. in ground on slight N.E. slope for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face,</p> <p>A Pine 28 ins. diam. brs. N. 8° E. 72 lks. dist.</p> <p>marked <math>\frac{1}{4}</math> S.B.T.</p> <p>A Pine 9 ins. diam. brs. S. 77° E. 50 lks. dist.</p> <p>marked <math>\frac{1}{4}</math> S.B.T.</p>	
80.00	<p>Set a basalt stone 18 x 12 x 6 ins. in mound of stone in open glade on level for Cor. to Secs. 35, 36, 1 and 2, marked with 5 notches on W. and one notch on E. edges.</p> <p>A Pine 8 ins. diam. brs. N. 79° W. 226 lks. dist.</p> <p>marked T. 4 S., R. 30 E., S. 35 B.T.</p> <p>No other trees near. Raised a mound of stone alongside in lieu of pits.</p> <p>Land; surface undulating,</p> <p>Soil; 3rd and 2nd rate, Pine, Tamarack and Fir timber with open glades. Good grass.</p>	
	<p>S. 89° 51' E. on a true line along the S. Bdy. of Sec. 36,</p> <p style="text-align: right;">Var. 19° 30' E.</p> <p>Undulating and descending,</p>	
40.00	<p>Set a basalt stone 18 x 12 x 5 in. on level in open glade in mound of stone for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face.</p> <p>Raised mound of stone alongside in lieu of pits.</p>	
80.00	<p>The Cor. to Tps. 4 and 5 S. Rs. 30 and 31 E.</p> <p>Descent about 100 ft.</p>	