

Subdivisional Lines of T. 4 S., R. 30 E. W.M.

Chains		Feet
	E. on a random line bet. Secs. 2 and 11. Var. 23° 45' E.	
	Descending,	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
59.50	A brook 10 lks. wide, course N.	-250
80.18	Intersected N. and S. line 38 lks. S. of Cor. to Secs. 1, 2, 11 and 12 from which Cor. I run, S. 89° 44' W. on a true line bet. Secs. 2 and 11 Var. 24° 45' E.	+100
40.09	A Pine 20 ins. diam. on S. slope, near brook for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. side. A Pine 22 ins. diam. brs. N. 31° W. 18 lks. dist. marked $\frac{1}{4}$ S. B.T. A Pine 10 ins. diam. brs. S. 60° E. 49 lks. dist. marked $\frac{1}{4}$ S.B.T.	
80.18	The Cor. to Secs. 2, 3, 10 and 11. Land; surface broken, Soil; 3rd and 2nd rate, some Pine, Fir and Tamarack. Timber on E. 50 Chs. W., 30 Chs. open prairie. Good grass.	
	N. bet. Sec. 2 and 3. Var. 23° 45' E.	
21.00	Enter timber, and begin descent.	
36.50	A spring branch and ravine, course N.E. Descent 150 ft.	
40.00	Set a basalt stone 15 x 8 x 6 ins. 10 ins. in ground on E. slope for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. A Pine 22 ins. diam. brs. E. 65 lks. dist. marked $\frac{1}{4}$ S. B.T., A Pine 20 ins. diam. brs. N. 58° W. 46 lks. dist. marked $\frac{1}{4}$ S.B.T. and, Leave timber, descent 50 ft.	
64.00	A Ravine, course N.E., and leave timber	
68.75	Intersected N. Bdy. 7.02 Chs. W. of Cor. to Secs. 34 & 35	