

Subdivisional Lines of T. 4 S., R. 30 E. W.M.

Chains		Feet
	timber with large open glades. Good grass.	
	N. bet. Sec. 15 and 16,	
	Var. 21° 30' E.	
27.50	Wagon road, course N.W. and S.E.	
40.00	Set a basalt stone 18 x 10 x 6 ins. in mound of stone on rocky ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. A Pine 14 ins. diam. brs. N. 67° E. 150 lks. dist. marked $\frac{1}{4}$ Sec. B.T. no other trees.	
80.00	Descent about 200 ft., set a basalt stone 20 x 6 x 5 ins. in mound of stone on N.W. slope for Cor. to Secs. 9, 10, 15 and 16, marked with 4 notches on S. and 3 notches on E. edges. A Pine 20 ins. diam. brs. N. 55° E. 20 lks. dist. marked T. 4 S., R. 30 E., S 10 B.T. A Pine 20 ins. diam. brs. S. 56° E. 58 lks. dist. marked T. 4 S., R. 30 E., S. 15 B.T. A Pine 24 ins. diam. brs. S. 67° W. 24 lks. dist. marked T. 4 S., R.30 E., S. 16 B.T. A Pine 12 ins. diam. brs. N. 40° W. 24 lks. dist. marked T. 4 S., R. 30 E., S. 9 B.T. Land; surface rolling and sloping N. Soil; 3rd and 2nd rate, scattering open Pine timber with large open glades. Good grass.	
	E. on a random line bet. Secs. 10 and 15.	
	Var. 21° 00' E.	
	Along N. slope, rolling	
40.00	Set temp $\frac{1}{4}$ Sec. Cor.	
73.50	Spring branch, course N.W.	
79.78	Intersected N. and S. line 22 lks. N. of Cor. to Secs. 10, 11, 14 and 15, thence I run, N. 89° 51' W. on a true line bet. Secs. 10 and 15. Var. 19° 00' E	