

## Exterior Lines of T. 4 S., R. 31 E., W.M.

Chains		Feet
	and Fir. Good grass in openings. Some good farming land.	
	N. on the W. Bdy. of Sec. 7,	
		Var. 21° 00' E.
22.00	Leave heavy timber, course E. and W.	
40.00	Set basalt stone 14 x 12 x 12 on S. slope in mound of stone for $\frac{1}{4}$ Sec. Cor.	
79.00	Enter timber, course E. and W.	
80.00	Set basalt stone 16 x 10 x 8 on N.W. slope for Cor. to Secs. 6, 7, 1 and 12.	
	A Pine 12 ins. diam. brs. N. 34° E. 30 lks. dist.	
	" " 8 " " " S. 45° E. 27 lks. dist.	
	" " 16 " " " S. 54° W. 34 lks. dist.	
	" " 13 " " " N. 35° W. 45 lks. dist.	
	Land; surface rolling,	
	Soil; 2nd 1st and 3rd rates. Some timber, Pine, Tamarack and Fir. Good grass. Some good farming land.	
	N. on the W. Bdy of Sec. 6,	
		Var. 21°45'E
40.00	Set basalt stone 18 x 8 x 7 on steep N. slope for $\frac{1}{4}$ Sec. Cor.	
	A Tamarack, 12 ins. diam. brs. E. 12 lks. dist.	
	" " 10 " " " N. 80° W. 10 lks. dist.	
50.00	A rivine opens, W..	-400
54.00	Leave timber, course E. and W.	
65.74	To a point on the S. Bdy. of Tp. 3 S., R. 30 E., 790 lks. W. of the Cor. to Tp. 3 S., Rs. 30 and 30 $\frac{1}{2}$ E. Set a basalt stone 18 x 8 x 8 and post in mound of stone at this point for Cor. to Tps. 4 S., Rs. 30 and 31 E. No trees.	
	Land; surface very broken,	
	Soil; 2nd and 3rd rate, heavy timber, Pine, Tamarack & Fir. Some underbrush.	
		Oct. 18, 1880