

## Exterior Lines of T. 4 S., R. 31 E. W.M.

Chains	Feet
	6 and 7.
	A Fir 10 ins. diam. brs. N. 65° E. 17 lks. dist.
	" " 8 " " " S. 33° E. 25 lks. dist.
	" " 12 " " " S. 63° W. 38 lks. dist.
	" Fir 6 " " " N. 54° W. 25 lks. dist.
	Land; surface mountainous.
	Soil; 3rd and 2nd rate. Timber irregular, heavy in places.
	Pine, Tamarack and Fir. Good grass in openings.
	N. on the E. Bdy. of Sec. 1,
	Var. 21°00'E
6.50	Wagon road, course N.E. and S.W.
40.00	Set basalt stone 17x10x8 on S.E. slope for $\frac{1}{4}$ Sec. Cor.
	A Tamarack 12 ins. diam. brs. E. 135 lks. dist.
	" Pine 18 ins. diam. brs. N. 67° W. 108 lks. dist.
65.64	Intersected S. Bdy. of Tp. 3 S., R. 31 E. 21,24 Chs. W.
-	of Cors. to Secs. 35 and 36, and set Pine post on level
	for Cor. to Tps 4 S., Rs. 31 and 32 E., from which,
	A Pine 6 ins. diam. brs. S. 54° E. 20 lks. dist.
	" " 8 " " " S. 42° W. 26 lks. dist.
	Land; surface mountainous.
	Soil; 3rd and 2nd rate, mostly heavy timber. Some open
	glades. Pine, Tamarack and Fir. Some grass.
	Subdivisional Lines of Tp. 4 S., R. 31 E. W.M.
	Surveyed by George S. Pershin, U.S. Deputy Surveyor,
	Under Contract No. 373,
	Dated Sept. 17, 1880
	N. bet. Secs. 35 and 36,
	Var. 19°30'E
3.00	Lemmon's house brs. W. 75 lks.
17.50	Wagon road, course N.W. and S.E.
36.00	" " " N.E. and S.W.
40.00	Set basalt stone 15 x 12 x 8 on S. slope in mound of
	stone for $\frac{1}{4}$ Sec. Cor.
80.00	Set basalt stone 20 x 10 x 8 on slight N. slope and post