

Subdivisional Lines of T. 4 S., R. 31 E. W.M.

Chains		Feet
	<p>in mound of stone for Cor. to Secs. 25, 26, 35 and 36. Land; surface undulating, Soil; 3rd, 2nd and 1st rate. Good grass. Some good farming land on S. $\frac{1}{2}$ mile. A few scattering Pine timber trees.</p>	
	<p>E. on a random line bet. Secs. 25 and 36. Var. 20°E.</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.88	<p>Intersected E. Bdy, 16 lks. S. of Cor. to Secs. 25 & 36, from which Cor. I run, S. 89° 53' W. on a true line bet. Secs. 25 and 36, Var. 20°00'E</p>	
39.94	<p>Set pine post on level for $\frac{1}{4}$ Sec. Cor. A Pine 12 ins. diam. brs. N. 58° E. 18 lks. dist. " " 10 " " " S. 12° W. 49 " "</p>	
79,88	<p>The Cor. to Secs. 25, 26, 35 and 36. Land; surface undulating, Soil; 2nd & 3rd rate. Some Pine timber. Good grass. Land well adapted to farming.</p>	
	<p>N. bet. Sec. 25 and 26, Var. 20°00'E.</p>	
40.00	Set basalt stone 16 x 12 x 5 on slight N.W. slope for $\frac{1}{4}$ Sec. Cor.	
80.00	<p>Set Pine post on level for Cor. to Secs. 23, 24, 25 & 26. A Pine 4 ins. diam. brs. N. 67° E. 10 lks. dist. " " 24 " " " S. 28° E. 76 " " " " 20 " " " S. 27° W. 78 " " " " 18 " " " N. 85° W. 65 " "</p>	
	<p>Land; surface undulating, Soil; 2nd & 1st rate, scattering Pine timber. Good grass. Larger part good farming land.</p>	
	<p>E. on a random line bet. Secs. 24 and 25. Var. 19°45'E.</p>	