

## Subdivisional Lines of T. 4 S., R. 31 E. W.M.

Chains		Feet
	N. 89° 51' W. on a true line bet. Secs. 1 and 12, Var. 21°00'E.	
13.00	Wagon road, course N.E. and S.W.	
27.00	A ravine opens S.W.	
40.13	Set basalt stone 14 x 10 x 7 on S.W. slope for $\frac{1}{4}$ Sec. Cor., A Pine 18 ins. diam. brs. N. 68° W. 77 lks. dist. A Pine 22 ins. diam. brs. S. 63° E. 48 lks. dist.	
80.26	The Cor. to Secs. 1, 2, 11 and 12. Land; surface mountainous. Soil; 3rd and 2nd rate, mostly heavy Pine, Tamarack & Fir timber with open glades. Good bunch grass in open timber.	
	N. on a random line bet. Sec. 1 and 2. Var. 21°00'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
65.68	Intersected N. Bdy. 12 lks. W. of Cor. to Secs. 1 and 2 from which Cor. I run, S. 00' W. on a true line bet. Secs. 1 and 2, Var. 20° 00' E	
25.68	Set basalt stone 18 x 8 x 7 on S. slope for $\frac{1}{4}$ Sec. Cor., A Pine 22 ins. diam. brs. S. 68° E. 70 lks. dist. A Pine 28 ins. diam. brs. S. 74° W. 104 lks. dist.	
65.68	The Cor. to Secs. k, 2, 11 and 12. Land; surface mountainous. Soil; 3rd and 2nd rate, heavy Pine, Tamarack and Fir timber with open glades. Some grass.	-400
	N. bet. Secs. 34 and 35. Var. 19°30'E.	
40.00	Set basalt stone 18 x 10 x 7 in mound of stone on S. $\frac{1}{4}$ slope for $\frac{1}{4}$ Sec. Cor.	
78.50	Snipe Creek, 12 lks. wide, course, E.	
80.00	Set basalt stone 20 x 10 x 7 ins. in mound of stone on slight S. slope for Cor. to Secs. 26, 27, 34 and 35.	