

Subdivisional Lines of T. 4, S., R. 31 E., W. M.

Chains		Feet
	<p>A Pine 48 ins. diam. brs. N. 56° W. 206 lks. dist. No other trees.</p>	
58.00	Geor. Skelton's house brs. S. 350 lks.	
79.44	<p>The cor. to Secs. 10, 11, 14, and 15. Land; surface undulating, Soil; 1st and 2nd rate. Good grass. Some scattering Pine timber. Excellent farming land. October 23, 1880</p>	- 40
	<p>N. bet. Secs. 10 and 11. Var. 21° 00' E</p>	
40.00	<p>Set basalt stone 18 x 12 x 4 on level in mound of stone for $\frac{1}{4}$ Sec. Cor. No trees.</p>	
	Mr. Bristow's house brs. N. 36° E.	
55.00	" " " " E.	
75.00	Begin ascent of mountain, ridge proper.	
80.00	<p>Set basalt stone 16 x 12 x 4 on S. face of ridge for Cor. to Secs. 2, 3, 10 and 11. A Pine 22 ins. diam. brs. N. 88° E. 73 lks. dist. " " 12 " " " S. 71° W. 210 lks. dist. " " 12 " " " N. 73° W. 170 lks. dist. No other trees. Land; surface nearly level. Soil; 1st and 2nd rate. Some scattering Pine timber on N. $\frac{1}{2}$ mile. Good grass. Excellent farming land.</p>	
	<p>E. on a random line bet. Sec. 2 and 11. Var. 20° 00' E.</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.70	<p>Intersected N. and S. line 46 lks. N. of Cor. to Sec. 1, 2, 11 and 12 from which Cor. I run. N. 89° 40' W. on a true line bet. Secs. 2 and 11.</p>	
	Var. 21° 00' E	
39.85	<p>Set basalt stone 16 x 10 x 7 on W. slope for $\frac{1}{4}$ Sec. Cor.</p>	