

Subdivisional Lines of T. 4 S., R. 31 E., W.M.

| Chains | | Feet |
|--------|---|-----------------|
| | E. on a random line bet. Secs. 27 and 34. | |
| | | Var. 21° 00' E. |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.02 | Intersected N. and S. line 18 lks. N. of Cor. to Secs, 26, 27, 34 and 35, from which Cor. I run, N. 89° 52' W. on a true line bet. Secs. 27 and 34. | |
| | | Var. 21° 30' E. |
| 1.80 | Snipe Creek, 15 lks. wide, course S. | |
| 40.01 | Set basalt stone 14 x 12 x 10 on slight S. slope for $\frac{1}{4}$ Sec. Cor. | |
| 80.02 | The Cor. to Secs. 27, 28, 33 and 34. Land; surface undulating, Soil; 3rd and 2nd rate. Some scattering Pine timber on E. $\frac{1}{2}$ mile. Some good farming land. | |
| | N. bet. Sec. 27 & 28, | |
| | | Var. 21° 00' E |
| 40.00 | Set basalt stone 16 x 14 x 5 on S. slope in mound of stone for $\frac{1}{4}$ Sec. Cor. | |
| 74.50 | Snip Creek, 20 lks. wide, course S.E. | |
| 80.00 | Set basalt stone 18 x 12 x 10 on mound of stone on S.W. slope for Cor. to Secs. 21, 22, 27 and 28. | |
| | A Pine 16 ins. diam. bts. S. 64° W. 244 lks. dist. No other trees. | |
| | Land; surface undulating, | |
| | Soil; 3rd and 2nd rate. Some scattering Pine timber along creek. Good grass. Some good farming land. | |
| | E. on a random line bet. Sec. 22 and 27, | |
| | | Var. 20° 50' E |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.16 | Intersected N. and S. line 62 lks. N. of Cor. to Secs. 22, 23, 26 and 27, from which Cor. I run, N. 89° 33' W. on a true line bet. Secs. 22 and 27, | |
| | | Var. 20° 15' E. |