

Subdivisional Lines of T. 4 S., R. 31 E. W. M.

Chains		100
40.04	<p>S. 89° 41' W. on a true line bet. Secs. 28, and 33.                      Var. 21° 00' E.                      Set basalt stone 16 x 12 x 10 in mound of stone on S.                      slope for <math>\frac{1}{4}</math> Sec. Cor.</p>	
80.08	<p>The cor. to Secs. 28, 29, 32 and 33.                      Land; surface undulating and sloping S.E.                      Soil; 3rd rate. Good grass, mostly adapted to grazing.                      Some good farming land.</p>	
40.00	<p>N. bet. Secs. 28 and 29.                      Var. 21° 00' E.                      Set basalt stone 17 x 10 x 10 ins. in mound of stone                      on E. slope for <math>\frac{1}{4}</math> Sec. Cor.</p>	
80.00	<p>Set basalt stone 20 x 10 x 8 in Sag, in point of timber,                      slight N.E. slope for Cor. to Secs. 20, 21, 28 &amp; 29                      A Pine 12 ins. diam. brs. N. 86° E. 30 lks. dist.                      " " 14 " " " S. 46° E. 84 lks. dist.                      " " 11 " " " S. 34° W. 172 lks. dist                      " " 10 " " " N. 66° W. 84 lks. dist.</p>	
	<p>Land; surface undulating,                      Soil; 3rd and 2nd rate, excellent grass. Some Pine                      timber. Small part farming land.</p>	
40.00	<p>E. on a random line bet. Secs. 21 and 28.                      Var. 20° 50' E.                      Set post for temp. <math>\frac{1}{4}</math> Sec. Cor.</p>	
79.96	<p>Intersected N. and S. line 52 lks. S. of Cor. to Secs.                      21, 22, 27 and 28, from which cor. I run,                      S. 89° 38' W. on a true line bet. Secs. 21 and 28.</p>	
6.00	<p>Var. 20° 50' E.                      Snipe Creek, 20 lks. wide, course S.</p>	
39.98	<p>Set basalt stone 18 x 12 x 12 on E. slope in mound                      of stone for <math>\frac{1}{4}</math> Sec. Cor.</p>	
79.96	<p>The cor. to Secs. 20, 21, 28 and 29.                      Land; surface undulating</p>	
	<p>Soil; 2nd and 3rd rate. Good grass. Some good farming</p>	