

Subdivisional Lines of T. 4 S., R. 31 E., W.M.

Chains		Feet
	Fir timber, with some open glades. Some good farming land.	
	E. on a random line bet. Sec. 17 and 20, Var. 18° 45' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.04	Intersected N. and S. line 26 lks. S. of Cor. to Secs. 16, 17, 20 and 21, from which Cor. I run, S. 89° 41' W. on a true line bet. Sec. 17 and 20. Var. 21° 00' E.	
40.02	Set basalt stone 16 x 14 x 8 on S.E. slope for $\frac{1}{4}$ Sec. Cor. A Pine 12 ins. diam. brs. S. 54° W. 121 lks. dist.	
	No trees N.	
80.04	The Cor. to Secs. 17, 18, 19 and 20 Land; surface rolling, Soil; 3rd and 2nd rate. Scattering Pine timber, good grass. Sec. 20, is about $\frac{1}{4}$ covered with heavy Pine Tamarack and Fir timber. About 1/8 is farming land.	+100
	W. on a random line bet. Sec. 18 and 19. Var. 18° 45' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.60	Intersected W. Bdy, 28 lks. N. of Cor. to Secs. 18 and 19, from which Cor I run, N. 89° 48' E. on a true line bet. Secs. 18 and 19. Var. 17° 00' E.	
39.60	Set basalt stone 17 x 8 x 7 on E. slope for $\frac{1}{4}$ Sec. Cor. A Pine 10 ins. diam. brs. N. 73° E. 24 lks. dist. " " 10 ins. " " S. 42° E. 40 " "	
79.60	The Cor. to Secs. 17, 18, 19 and 20 Land; surface rolling, Soil; 3rd and small part 2nd rate. Some scattering Pine timber. Good grass. Sec. 19 is mostly grazing land.	-100
	N. bet. Secs. 17 and 18.	