

## Exterior Lines, T. 4 S., R. 32 E., W. M.

Chains	
	<p>A pine, 10 ins. diam., brs. S.27°W., 74 lks. dist.</p> <p>A pine, 9 ins. diam., brs. N.28°W., 87 lks. dist.</p> <p>Land; surface very rolling.</p> <p>Soil; 3rd &amp; 2nd rate.</p> <p>Mostly heavy pine, tamarack &amp; fir timber with open glades.</p> <p>Some underbrush, good grass in open glades.</p>
	<p>N. on E. Bdy. of Sec. 24.</p> <p style="text-align: right;">Var. 19°45'E.</p>
40.00	<p>Set basalt stone, 18 x 12 x 5, in ravine, on W. bank of brook, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>A tamarack, 20 ins. diam., brs. N.45°E., 26 lks. dist.</p> <p>A fir, 8 ins. diam., brs. S.42°W., 60 lks. dist.</p>
41.00	In brook, 12 lks. wide, course from N. to S.E.
47.00	Leave brook, 12 lks. wide,, course from N.E.
80.00	<p>Set basalt stone, 14 x 12 x 4 on S.W.slope for Cor. to Secs. 13, 24, 18 &amp; 19.</p> <p>A pine, 8 ins. diam., brs. N.24°E., 135 lks. dist.</p> <p>A " 10 " " " S.12°E., 74 lks. dist.</p> <p>A " 10 " " " S.53°W., 94 " "</p> <p>A " 22 " " " N.23°W., 79 " "</p> <p>Land; surface very rolling.</p> <p>Soil; 2nd &amp; 3rd rate.</p> <p>Heavy pine, tamarack &amp; fir timber, with open glades.</p> <p>Some underbrush. Good grass in glades.</p>
	<p>N. on E. Bdy. of Sec. 13.</p> <p style="text-align: right;">Var. 20°30'E.</p>
40.00	<p>Set basalt stone, 18 x 12 x 8 on S. slope for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>A pine, 17 ins. diam., brs. S.54°E., 85 lks. dist.</p> <p>A " 15 " " " N.68°W., 82 " "</p>
56.00	On ridge, course E. & W.
73.50	A brook, 6 lks. wide, course E.
80.00	<p>Set basalt stone, 18 x 8 x 5 on steep S. side of rocky point, for Cor. to Secs. 12, 13, 7 &amp; 18.</p> <p>A pine, 14 ins. diam., brs. N.62°E., 16 lks. dist.</p>