

Subdivisional Lines, T.4 S.,R.32 E.,W. M.

Chains 79.46	<p>Intersected E. Bdy., 19 lks. N. of Cor. to Secs. 13 & 24, from which Cor., I run N.89°52'W. on true line bet. Secs. 13 & 24. Var.20°30'E.</p>
39.73	<p>Set basalt stone, 16 x 12 x 8 on slight E. slope for $\frac{1}{4}$ Sec. Cor. A pine, 20 ins. diam.,brs. N.5°W., 95 lks. dist. A " 12 " " " S.43°E.,55 " "</p>
79.46	<p>The Cor. to Secs. 13, 14, 23 & 24. Land; surface rolling. Soil; 2nd & 1st rate. Heavy pine, tamarack & fir timber, with open glades. Some willow and young timber underbrush.</p>
	<p>N. bet. Secs. 13 & 14. Var.18°15'E.</p>
40.00	<p>Set basalt stone, 17 x 10 x 4 ins., in small open glade, for $\frac{1}{4}$ Sec. Cor., on level. A pine, 12 ins. diam.,brs. N.42°E., 52 lks. dist. A pine, 26 ins. diam.,brs. S.77°W., 132 lks. dist.</p>
80.00	<p>Set basalt stone, 16 x 12 x 5, on slight W. slope, for Cor. to Secs. 11, 12, 13 & 14. A pine, 20 ins. diam.,brs. N.50°E., 128 lks. dist. A " 20 " " " S.54°E., 105 " " A " 12 " " " S.71°W., 40 " " A " 6 " " " N.47°W., 111 " "</p> <p>Land; surface rolling. Soil; 3rd & 2nd rate. Heavy pine, tamarack & fir timber, with open glades. Good grass in glades, some underbrush.</p>
	<p>E. on random line bet. Secs. 12 & 13. Var.19°00'E.</p>
40.00	<p>Set post for temp. $\frac{1}{4}$ Sec. Cor.</p>
79.58	<p>Intersected E. Bdy., 14 lks. N. of Cor. to Secs. 12 & 13, from which Cor., I run</p>