

Subdivisional Lines, T.4 S., R.32 E., W. M.

Chains	Land; surface rolling. Soil; 2nd rate. Heavy pine, tamarack & fir timber, with open glades. Some dense young growths of young timber. June 24, 1881.
	N. bet. Secs. 31 & 32. Var. 19°15'E.
15.50	Enter timber, course S.E. & N.W.
40.00	Set pine post, on slight N. slope, for $\frac{1}{4}$ Sec. Cor. A pine, 40 ins. diam., brs. N.38°E., 82 lks. dist. A " 5 " " " S.53°W., 25 " "
56.50	A cabin brs. W., about 8 chs. dist.
80.00	Set basalt stone, 16 x 10 x 8 ins., in open glade, on level, for Cor. to Secs. 29, 30, 31 & 32. A pine, 8 ins. diam., brs. N.67°E., 333 lks. dist. A " 18 " " " S.56°E., 314 " " A " 12 " " " S.62°W., 370 " " A " 8 " " " N.54°W., 232 " "
	Land; surface slightly undulating. Soil; 1st & 2nd rate. Pine & tamarack timber, with open glades, good grass. All good farming land.
	E. on random line bet. Secs. 29 & 32. Var. 20°00'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.28	Intersected N. & S. line, 14 lks. S. of Cor. to Secs. 28, 29, 32 & 33, from which Cor., I run S.89°54'W. on true line bet. Secs. 29 & 32. Var. 21°40'E.
40.14	Drove pine post, in soft slightly marshy ground, for $\frac{1}{4}$ Sec. Cor.
45.00	Cabin, N. of line about 4 chs. dist., and large garden.
48.00	Enter timber, course N. & S.
80.28	The Cor. to Secs. 29, 30, 31 & 32. Land; surface level.