

Subdivisional Lines, T.4 S., R.32 E., W. M.

Chains	Soil; 1st rate. Good grass. Pine timber on W. 32 chs., all good farming land.
	W. on random line bet. Secs. 30 & 31. Var. 20°00'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.86	Intersected W. Bdy. at Cor. to Secs. 30 & 31, from which Cor., I run E. on true line bet. Secs. 30 & 31. Var. 20°00'E.
39.86	Set basalt stone, 18 x 10 x 5, on level, for $\frac{1}{4}$ Sec. Cor. A pine, 13 ins. diam., brs. N.12°E., 236 lks. dist. A " 9 " " " S. 8°E., 114 " "
77.50	Owens Creek, 12 lks. wide, course S.
79.86	The Cor. to Secs. 29, 30, 31 & 32. Land; surface slightly undulating. Soil; 1st & 2nd rate. Pine timber with open glades, good grass in glades. Good farming land. June 25, 1881.
	N. bet. Secs. 29 & 30. Var. 20°00'E.
22.00	Owens Creek, 12 lks. wide, course S.W.
40.00	Set basalt stone, 18 x 8 x 5, on level, W. of creek, for $\frac{1}{4}$ Sec. Cor. A pine, 20 ins. diam., brs. N.65°E., 122 lks. dist. A " 10 " " " N.70°W., 37 " "
80.00	Set basalt stone, 15 x 8 x 7, on slight S. slope, for Cor. to Secs. 19, 20, 29 & 30. A pine, 13 ins. diam., brs. N.34°E., 16 lks. dist. A " 14 " " " S.12°E., 26 " " A " 10 " " " N.34°W., 60 " "
	Open glade S.W. Land; surface slightly undulating. Soil; 1st & 2nd rate. Pine timber, with open glades, good grass.