

Subdivisional Lines, T.4 S., R.32 E., W. M.

Chains	E. on random line bet. Secs. 20 & 29. Var.19°45'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.48	Intersected N. & S. line, 28 lks. S. of Cor. to Secs. 20, 21, 28 & 29, from which Cor., I run S.89°48' W. on true line bet. Secs. 20 & 29. Var.20°30'E.
40.24	Set basalt stone, 20 x 10 x 5, in mound of stone, on S.W. slope, for $\frac{1}{4}$ Sec. Cor.
45.50	Enter timber, course, N.W. & S.E.
55.00	Owens Creek, 15 lks. wide, course S.
80.48	The Cor. to Secs. 19, 20, 29 & 30. Land; surface on E. $\frac{1}{2}$ mile, rolling, W. $\frac{1}{2}$ mile, undulating. Soil; 1st, 2nd & 3rd rate. Pine & tamarack timber on W. 35 chs. Good grass on prairies.
	W. on random line bet. Secs. 19 & 30. Var.19°45'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.56	Intersected W. Bdy., 8 lks. S. of Cor. to Secs. 19 & 30, from which Cor., I run S.89°57'E. on true line bet. Secs. 19 & 30. Var.19°45'E.
28.00	Enter timber, courses S.W. & n.e.
39.56	Set post, in ground, for $\frac{1}{4}$ Sec. Cor., on level, in open glade. A pine, 13 ins. diam., brs. N.14°E., 329 lks. dist. AA pine, 20 ins. diam., brs. S.10°E., 238 lks; dist.
79.56	The Cor. to Secs. 19, 20, 29 & 30. Land; surface nearly level. Soil; 1st & small part 2nd rate. Pine timber, with open glades, good grass in glades.
	N. bet. Secs. 19 & 20. Var.19°45'E.
20.00	Elim Connell's house brs. N.75°W.