

Subdivisional Lines; T.4 S., R.32 E., W. M.

Chains	
30.00	Elim Connell's house brs. S.60°W.
40.00	Set pine post, on level, for $\frac{1}{4}$ Sec. Cor. A pine, 40 ins. diam., brs. N.15°E., 36 lks. dist. A pine, 13 ins. diam., brs. S.18°W., 102 lks. dist.
80.00	Set basalt stone, 18 x 10 x 4, on slight S.W. slope, for Cor. to Secs. 18, 17, 19 & 20. A pine, 12 ins. diam., brs. N.33°E., 67 lks. dist. A pine, 22 ins. diam., brs. S.68°E., 145 lks. dist. A pine, 42 ins. diam., brs. S.6°W., 60 lks. dist. A pine, 6 ins. diam., brs. N.40°W., 102 lks. dist. Land; surface undulating. Soil; 1st & 2nd rate. Heavy pine timber, with open glades, grass in glades.
<hr/> E. on random line bet. Secs. 17 & 20;	
Var.19°30'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.38	Intersected N. & S. line, 28 lks. N. of Cor. to Secs. 16, 17, 20 & 21, from which Cor., I run N.89°48' W. on true line bet. Secs. 17 & 20.
Var.19°20'E.	
16.50	A brook, 6 lks. wide, course S.W.
40.19	Set basalt stone, 18 x 14 x 5, on W. slope, for $\frac{1}{4}$ Sec. Cor. A pine, 10 ins. diam., brs. N.2°E., 135 lks. dist. A pine, 10 ins. diam., brs. S.28°E., 87 lks; dist.
80.38	The Cor. to Secs. 17, 18, 19 & 20. Land; surface rolling. Soil; 2nd, 3rd & 1st rate. Pine, tamarack & fir timber, with open glades, grass in glades.
<hr/> W. on random line bet. Secs. 18 & 19.	
Var.19°30'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.50	Intersected W. Bdy., 14 lks. S. of Cor. to Secs. 18 & 19. from which Cor., I run