

Subdivisional Lines, T.4 S., R.32 E., W. M.

Chains	
	<p>S.89°58' E. on true line bet. Secs. 18 & 19. Var.19°45'E.</p>
16.00	Fence & field, course N.E. & S.W.
39.60	Set basalt stone, 17 x 12 x 5, in mound of stone, on level, in John Connell's field, for $\frac{1}{4}$ Sec. Cor.
50.50	Leave field, enter timber, course N. & S.
79.60	The Cor. to Secs. 17, 18, 19 & 20. Land; surface undulating. Soil; 1st & 2nd rate. Pine timber outside of field, grass in field. John Connell's house cannot be seen from line.
<hr/>	
	<p>N. bet. Secs. 17 & 18. Var.19°30'E.</p>
40.00	Set basalt stone, 14 x 10 x 10, on S. slope, for $\frac{1}{4}$ Sec. Cor. A pine, 28 ins. diam., brs. S.70°E., 28 lks. dist. A pine, 12 ins. diam., brs. N.63°W., 150 lks. dist.
65.00	In ravine, opens S.W.
80.00	Set basalt stone, 16 x 12 x 5, on E. face of ridge, for Cor. to Secs. 7, 8, 17 & 18. A fir, 10 ins. diam., brs. N.63°E., 38 lks. dist. A fir, 20 ins. diam., brs. S.74°E., 70 lks. dist. A pine, 18 ins. diam., brs. S.55°W., 10 lks. dist. A pine, 10 ins. diam., brs. N.33°W., 89 lks. dist. Land; surface rolling, N. part broken. Soil; 2nd & 3rd rate. Heavy pine, tamarack & fir timber, with open glades. Some dense thickets of young timber, grass in glades.
<hr/>	
	<p>E. on random line bet. Secs. 8 & 17. Var.20°00'E.</p>
40.00	Set post for temp. $\frac{1}{4}$ sec. Cor.
80.64	Intersected N. & S. line, 12 lks. N. of Cor. to Secs. 8, 9, 16 & 17, from which Cor., I run N.89°55'W. on true line bet. Secs. 8 & 17 Var.21°00'E.