

Exterior Lines, T.4 S., R.33 E., W. M.

Chains

A pine, 18 ins. diam., brs. S.13°W., 34 lks. dist.,
marked $\frac{1}{4}$ S., B.T.

41.00 A ravine, 20 ft. deep, course S.W.

69.00 On level plateau, about 80 ft. above creek bottom.

80.00 The Cor. to Tps. 4 & 5 S., Rs. 33 & 34 E.

Land; surface rolling, part nearly level.

Soil; 2nd & 3rd rate.

Some pine timber, mostly open.

Sept. 7, 1881.

I begin at the Cor. to Tps. 4 & 5 S., Rs. 33 & 34 E., and
I run

N. on E. Bdy. of Sec. 36.

Var. 18°15'E.

13.00 Enter timber, course E. & W.

40.00 Set basalt stone, 18 x 12 x 5 ins., 12 ins. in ground, for
 $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face.

A pine, 15 ins. diam., brs. N.30°E., 13 lks. dist.,
marked $\frac{1}{4}$ S., B.T.

A pine, 18 ins. diam., brs. S.18°W., 12 lks. dist.,
marked $\frac{1}{4}$ S., B.T.

80.00 Set basalt stone, 18 x 10 x 5 ins., 12 ins. in ground, on
slight S. slope, for Cor. to Secs. 25, 36, 30 & 31,
marked with one notch on S. and 5 notches on N. edges.

A pine, 14 ins. diam., brs. N.36°E., 68 lks. dist.,
marked T.4 S., R.34 E., S.30, B.T.

A pine, 38 ins. diam., brs. S.50°E., 47 lks. dist.,
marked T.4 S., R.34 E., S.31, B.T.

A pine, 6 ins. diam., brs. S.18°W., 56 lks. dist.,
marked T.4 S., R.33 E., S.36, B.T.

A tamarack, 11 ins. diam., brs. N.63°W., 98 lks. dist.,
marked T.4 S., R.33 E., S.25, B.T.

Land; surface undulating.

Soil; 2nd & 3rd rate.

Mostly heavy pine, tamarack & fir timber. Some open glades.