

Exterior Lines, T.4 S., R.33 E., W. M.

Chains	N. on E. Bdy. of Sec. 25.	Var. 19°00'E.
28.00	Large open glade.	
40.00	Set basalt stone, 18 x 12 x 7 ins., 12 ins. in ground, on slight S.W. slope, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. A pine, 28 ins. diam., brs. N.52°E., 180 lks. dist., marked $\frac{1}{4}$ S., B.T. No tree on W. side. Raised mound of stone alongside Cor.	
43.50	Enter timber, course N.W. & S.E.	
80.00	Set basalt stone, 12 x 8 x 7 ins., 8 ins. in ground, for Cor. to Secs. 24, 25, 19 & 30, marked with 2 notches on S. and 4 notches on N. edges. A pine, 8 ins. diam., brs. N.22°E., 64 lks. dist., marked T.4 S., R.34 E., S.19, B.T. A pine, 6 ins. diam., brs. S.38°E., 94 lks. dist., marked T.4 S., R.34 E., S.30, B.T. A pine, 8 ins. diam., brs. S.36°W., 17 lks. dist., marked T.4 S., R.33 E., S.25, B.T. A pine, 10 ins. diam., brs. N.50°W., 81 lks. dist., marked T.4 S., R.33 E., S.24, B.T. Land; surface undulating. Soil; 2nd & 3rd rate. Mostly heavy timber, with open glades.	
	N. on E. Bdy. of Sec. 24.	Var. 21°00'E.
	Irregular surface.	
40.00	Set basalt stone, 16 x 12 x 4 ins., 11 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. A tamarack, 6 ins. diam., brs. S.28°E., 40 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 8 ins. diam., brs. N.42°W., 63 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80:00	Set basalt stone, 17 x 12 x 5 ins., 12 ins. in ground, on S. side of spring branch, for Cor. to Secs. 13, 24, 18 & 19.	