

Exterior Lines, T.4 S., R.33 E., W. M.

Chains

marked with 3 notches on S. and 3 notches on N. edges.

A pine, 7 ins. diam., brs. N.67°E., 116 lks. dist.,
marked T.4 S., R.34 E., S.18, B.T.

A pine, 12 ins. diam., brs. S.84°E., 142 lks. dist.,
marked T.4 S., R.34 E., S.19, B.T.

A pine, 10 ins. diam., brs. S.76°W., 75 lks. dist.,
marked T.4 S., R.33 E., S.24, B.T.

A pine, 10 ins. diam., brs. N.67°W., 59 lks. dist.,
marked T.4 S., R.33 E., S.13, B.T.

Land; surface undulating.

Soil; 2nd rate, small part 1st rate.

Heavy pine, tamarack & fir timber, with open glades.

N. along E. Bdy. of Sec. 13.

Var. 20°30'E.

0.10 Spring branch, course S.E. Ascending.

40.00 Set basalt stone, 16 x 10 x 8 ins., 11 ins. in ground, for
¼ Sec. Cor., marked ¼ on W. face.

A pine, 22 ins. diam., brs. N.84°E., 70 lks. dist.,
marked ¼ S., B.T.

A pine, 20 ins. diam., brs. S.46°W., 23 lks. dist.,
marked ¼ S., B.T.

80.00 Set basalt stone, 16 x 14 x 10 ins., 11 ins. in ground, for
Secs. 12, 13, 7 & 18, marked with 4 notches on S. edge
and 2 notches on N. edge, (on level), from which,

A pine, 6 ins. diam., brs. N.54°E., 25 lks. dist.,
marked T.4 S., R.34 E., S.7, B.T.

A pine, 6 ins. diam., brs. S.82°E., 25 lks. dist.,
marked T.4 S., R.34 E., S.18, B.T.

A pine, 6 ins. diam., brs. S.38°W., 17 lks. dist.,
marked T.4 S., R.33 E., S.13, B.T.

A pine, 8 ins. diam., brs. N.68°W., 27 lks. dist.,
marked T.4 S., R.33 E., S.12, B.T.

Land; surface slightly rolling.

Soil; 2nd rate.

Alternate heavy timber and small open glades, pine, tamarack
and fir.

Sept. 8, 1881.