

Exterior Lines, T.4 S., R.33 E., W. M.

Chains

Cor. to Tps. 3 & 4 S., Rs. 33 & 34 E. marked with 6 notches on N., S., E. and W. edges, severally. Ascent 150 ft.

A pine, 6 ins. diam., brs. N.38°E., 80 lks. dist. marked T.3 S., R.34 E., S.31, B.T.

A pine, 16 ins. diam., brs. S.58°E., 48 lks. dist., marked T.4 S., R.34 E., S.6, B.T.

A pine, 15 ins. diam., brs. S.50°W., 13 lks. dist., marked T.4 S., R.33 E., S.1, B.T.

A pine, 12 ins. diam., brs. N.74°W., 23 lks. dist., marked T.3 S., R.33 E., S.36, B.T.

Land; surface part undulating and part broken.

Soil; 3rd rate.

Pine, tamarack & fir timber, heavy in places. Some open glades.

Sept. 9, 1881.

Resurvey W. Bdy. T.4 S., R.33½ E., W. M.  
As surveyed by Rufus S. Moore,  
Under Contract No. 451  
Dated June 12, 1882.

Resurvey of W. Bdy. From Cor. to Tps. 4 & 5 S., Rs. 33½ E.

I run

N. on W. Bdy. of Sec. 34.

Var. 18°15'E.

14.31 The Cor. to Tps. 4 & 5 S., R. 33 E., which is a post, 5 ins. sq., marked

T.4 S., R.34 E., S.31 on N.E.

T.4 S., R.33 E., S.36 on N.W.

T.5 S., R.33 E., S.1, on S.W. end

T.5 S., R.34 E., S.6 on S.E. faces, with

6 notches on each edge and

with mound of stone around post.

Destroyed marks referring to 33½ E.

27.25 Enter heavy timber, brs. E. & W.

54.56 The ¼ Sec. Cor.

80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor.