

W. Bdy. of T. 4 S., R. 33 $\frac{1}{2}$  E., W. M.

## Chains

A pine, 4 ins. diam., brs. N. 61° E., 41 lks. dist.,  
marked T. 4 S., R. 33 $\frac{1}{2}$  E., S. 22, B. T.

A tamarack, 7 ins. diam., brs. S. 67° E., 9 lks. dist.,  
marked T. 4 S., R. 33 $\frac{1}{2}$  E., S. 27, B. T.

Land; rolling hills.

Soil; 2nd & 3rd rate.

Heavily timbered with pine, fir & tamarack.

Undergrowth; pine & fir.

N. on W. Bdy. of Secs. 22.

Var. 21° E.

15.01 The Cor. to Secs. 19, 24, 25 & 30, which is a basalt stone  
12 x 8 x 7, marked with 4 notches on N. and 2 on S.  
edges; from which

A pine, 8 ins. diam., brs. N. 22° E., 64 lks. dist.,  
marked T. 4 S., R. 34 E., S. 19, B. T.

A pine, 6 ins. diam., brs. S. 38° E., 94 lks. dist.,  
marked T. 4 S., R. 34 E., S. 30, B. T.

A pine, 8 ins. diam., brs. S. 36° W., 19 lks. dist.,  
marked T. 4 S., R. 33 E., S. 25, B. T.

A pine, 10 ins. diam., brs. N. 50° W., 81 lks. dist.,  
marked T. 4 S., R. 33 E., S. 24, B. T.

Destroyed marks referring to Secs. 19 & 30.

55.20 The  $\frac{1}{4}$  Sec. Cor.

80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for  
Cor. to Secs. 15 & 22, marked

T. 4 S., R. 33 $\frac{1}{2}$  E. on E.

S. 15 on N. and

S. 22 on S. faces, with

3 notches on N. & S. faces,

from which

A pine, 20 ins. diam., brs. N. 65° E., 232 lks. dist.,  
marked T. 4 S., R. 33 $\frac{1}{2}$  E., S. 15, B. T.

A pine, 24 ins. diam., brs. S. 35° E., 284 lks. dist.,  
marked T. 4 S., R. 33 $\frac{1}{2}$  E., S. 22, B. T.