

W. Bdy. T.4 S., R. 33 $\frac{1}{2}$  E., W. M.

Chains	<p>Land; rolling hills.</p> <p>Soil; 2nd &amp; 3rd rate.</p> <p>Heavily timbered with pine, fir &amp; tamarack.</p>
14.85	<p>N. on W. Bdy. of Sec. 15.</p> <p style="text-align: right;">Var. 20°30'E.</p> <p>The Cor. to Secs. 18, 19, 13 &amp; 24, which is a basalt stone 17 x 12 x 5, marked with 3 notches on N. &amp; S. edges, from which</p> <p style="padding-left: 40px;">A pine, 7 ins. diam., brs. N.67°E., 116 lks. dist., marked T.4 S., R.34 E., S.18, B.T.</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., brs. S.84°E., 142 lks. dist., marked T.4 S., R.34 E., S.19, B.T.</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. S.76°W., 75 lks. dist., marked T.4 S., R.33 E., S.24, B.T.</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. N.67°W., 59 lks. dist., marked T.4 S., R.33 E., S.13, B.T.</p> <p>Destroyed marks referring to Secs. 18 &amp; 19.</p>
14.90	Spring branch, 3 lks. wide, runs S.E.
54.70	The $\frac{1}{4}$ Sec. Cor.
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 10 &amp; 15, marked</p> <p style="padding-left: 40px;">T.4 S., R.33<math>\frac{1}{2}</math> E. on E.</p> <p style="padding-left: 40px;">S.10 on N. and</p> <p style="padding-left: 40px;">S.15 on S. faces, with</p> <p style="padding-left: 40px;">4 notches on S. and</p> <p style="padding-left: 40px;">2 notches on N. edges, from which</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., brs. N.40°E., 65 lks. dist., marked T.4 S., R.33<math>\frac{1}{2}</math> E., S.10, B.T.</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. S.70°E., 189 lks. dist., marked T.4 S., R.33<math>\frac{1}{2}</math> E., S.15, B.T.</p>
	<p>Land; rolling hills.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir &amp; tamarack.</p> <p>Dense undergrowth of pine, fir &amp; tamarack.</p>
	<p>N. on W. Bdy. of Sec. 10.</p> <p style="text-align: right;">Var. 20°E.</p>