

W. Bdy., T.4 S., R.33 $\frac{1}{2}$ E., W. M.

Chains

- 14.63 The Cor. to Secs. 12, 13, 17 & 18, which is a basalt stone
16 x 14 x 10, marked with 4 notches on S. and 2 on N.
edges, from which
- A pine, 6 ins. diam., brs. N.54°E., 25 lks. dist.,
marked T.4 S., R.34 E., S.7, B.T.
- A pine, 6 ins. diam., brs. S.82°E., 25 lks. dist.,
marked T.4 S., R.34 E., S.18, B.T.
- A pine, 6 ins. diam., brs. S.38°W., 17 lks. dist.,
marked T.4 S., R.33 E., S.13, B.T.
- A pine, 8 ins. diam., brs. N.68°W., 27 lks. dist.,
marked T.4 S., R.33 E., S.12, B.T.

Destroyed marks referring to Secs. 7 & 18.

- 54.50 The $\frac{1}{4}$ Sec. Cor.
- 74.25 Spring branch, 3 lks. wide, runs N.W., 200 ft. below $\frac{1}{4}$
Sec. Cor. Ascend.
- 80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for
Cor. to Secs. 3 & 10, marked
- T.4 S., R.33 $\frac{1}{2}$ E., on E.
S.3 on N. and
S.10 on S. faces, with
5 notches on S. and
1 notch on N. faces,
on S.W. slope of hill, from which
- A pine, 7 ins. diam., brs. S.40°E., 20 lks. dist.,
marked T.4 S., R.33 $\frac{1}{2}$ E., S.10, B.T.
- A pine, 8 ins. diam., brs. N.75°E., 89 lks. dist.,
marked T.4 S., R.33 $\frac{1}{2}$ E., S.3, B.T.

Land; rolling hills.

Soil; 2nd & 3rd rate.

Heavily timbered with pine, fir & tamarack.

Dense undergrowth of pine & fir.

N. on W. Bdy. of Sec. 3.

Var. 20°45'E.

Ascend hill from Cor.

- 14.40 The Cor. to Secs. 1, 12, 6 & 7, which is a basalt stone,