

Subdivisional Lines, T.4 S., R.33 E., W. M.

| Chains | |
|--------|--|
| | Soil; 2nd & 3rd rate. Nearly all heavy timber, pine, tamarack & fir, with much thick under brush. Sept. 12, 1881. |
| | N. bet. Secs. 13 & 14. Var. 17°15'E. |
| | Slightly undulating plateau. |
| 40.00 | Set basalt stone, 20 x 16 x 4 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which A fir, 8 ins. diam., brs. S.40°E., 27 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 12 ins. diam., brs. S.9°W., 73 lks. dist., marked $\frac{1}{4}$ S., B.T. |
| 76.25 | A corral. |
| 77.00 | A cabin, 150 lks. W. |
| 78.50 | Leave corral. |
| 80.00 | Set basalt stone, 18 x 12 x 5 ins., 12 ins. in ground, for Cor. to Secs. 11, 12, 13 & 14, marked with 4 notches on S. and 1 notch on E. edges, from which A pine, 10 ins. diam., brs. N.34°E., 31 lks. dist., marked T.4 S., R.33 E., S.12, B.T. A pine, 10 ins. diam., brs. S.44°E., 11 lks. dist., marked T.4 S., R.33 E., S.13, B.T. A tamarack, 12 ins. diam., brs. S.3°W., 34 lks. dist., marked T.4 S., R.33 E., S.14, B.T. No tree N.W. Raised mound of stone alongside, in lieu of pits. |
| | Land; surface slightly undulating. |
| | Soil; 2nd & 3rd rate. |
| | Timber; nearly all killed by fire and mostly down, pine, tamarack & fir. |
| | E. on random line bet. Secs. 12 & 13. Var. 23°30'E. |
| 6.50 | A spring branch, course S.E. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. |