

Subdivisional Lines, T.4 S.,R.33 E.,W. M.

Chains

39.74 Set basalt stone, 18 x 10 x 8 ins., 12 ins. in ground, for
 $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which
 A pine, 15 ins. diam., brs. S.44°E., 63 lks. dist.,
 marked $\frac{1}{4}$ S., B.T.
 A pine, 9 ins. diam., brs. N.18°W., 24 lks. dist.,
 marked $\frac{1}{4}$ S., B.T.

79.74 The Cor. to Secs. 1, 2, 11 & 12.

Land; surface undulating.

Soil; 2nd & 3rd rate.

Mostly heavy pine, tamarack & fir timber.

Sept. 13, 1881.

N. bet. Secs. 34 & 35.

Var. 20°00'E.

17.50 Ben Selling's cabin, 2 chs. E.

22.00 Begin ascent.

34.50 Wagon road to hot sulphur Springs, course S.E. & N.W.

40.00 Set basalt stone, 20 x 12 x 8 ins., 15 ins. in ground, for
 $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face.

A pine, 14 ins. diam., brs. N.60°E., 70 lks. dist.,
 marked $\frac{1}{4}$ S., B.T.

Open glade on other side. Raised mound of stone along
 side, in lieu of pits.

48.50 A fresh water spring on line.

72.50 A brook, 10 lks; wide, course from N. to S.15°E.

78.50 Leave brook, from N.15°W.

80.00 Set basalt stone, 18 x 10 x 8 ins., 12 ins. in ground, for
 Cor. to Secs. 26, 27, 34 & 35, marked with 1 notch on
 S. and 2 notches on E. edges, from which

A pine, 16 ins. diam., brs. N.44°E., 78 lks. dist.,
 marked T.4 S., R.33 E., S.26, B.T.

A pine, 8 ins. diam., brs. S.36°E., 35 lks. dist.,
 marked T/4 S., R.33 E., S.35, B.T.

A pine, 22 ins. diam., brs. S.34°W., 18 lks. dist.,
 marked T.4 S., R.33 E., S.34, B.T.