

Exterior Lines, T.4 S.,R.34 E.,W. M.

Chains

- 76.00 Wagon road, course E. & W.
- 80.00 Set basalt stone, 13 x 10 x 7 ins., 8 ins. in ground, for
Cor. to Secs. 25, 30, 31 & 36, marked with 5 notches
on N. and 1 notch on S. edges, from which,
A pine, 10 ins. diam., brs. S.36°W., 20 lks. dist.,
marked T.4 S., R.33½ E., S.36, B.T.
A pine, 8 ins. diam., brs. N.74°W., 10 lks. dist.,
marked T.4 S., R.33½ E., S.25, B.T.
A pine, 10 ins. diam., brs. N.66°E., 60 lks. dist.,
marked T.4 S., R.34 E., S.30, B.T.
A pine, 15 ins. diam., brs. S.28°E., 48 lks. dist.,
marked T.4 S., R.34 E., S.31, B.T.

Land; gently rolling.

Soil; 1st & 2nd rates.

Heavily timbered with pine, 48 chs.

Scattering timber, 32 chs.

N. bet. Secs. 25 & 30.

Var. 20°E.

- 25.25 Ravine, course W.
- 40.00 Set basalt stone, 15 x 15 x 6 ins., 10 ins. in ground, for
¼ Sec. Cor., marked ¼ on W. face, from which,
A pine, 5 ins. diam., brs. S.89°E., 25 lks. dist.,
marked ¼ S., B.T.
A pine, 6 ins. diam., brs. N.60°W., 33 lks. dist.,
marked ¼ S., B.T.
- 44.35 Ravine, course W.
- 80.00 Set basalt stone, 15 x 10 x 8 ins., 10 ins. in ground, for
Cor. to Secs. 19, 24, 25 & 30, marked with 4 notches
on N. and 2 notches on S. edges, from which
A pine, 30 ins. diam., brs. S.56°W., 113 lks. dist.,
marked T.4 S., R.33½ E., S.25, B.T.
No other trees within limits.
Raised mound of stone alongside.
Land; rolling.
Soil; 2nd rate. Heavily timbered with pine, 80 chs.