

Exterior Lines, T. 5 S., R. 34 E., W. M.

Chains	
	<p>A pine, 7 ins. diam., brs. N.18°W., 97 lks. dist., marked T.4 S., R.34 E., S.33, B.T.</p> <p>A tamarack, 40 ins. diam., brs. S.66°W., 54 lks. dist., marked T.5 S., R.34 E., S.4, B.T.</p> <p>A pine, 12 ins. diam., brs. S.23°E., 70 lks. dist., marked T.5 S., R.34 E., S.3, B.T.</p> <p>Land; gently rolling.</p> <p>Soil; 1st & 2nd rate.</p> <p>Heavily timbered with pine, fir & tamarack.</p> <p>Dense undergrowth of pine & fir.</p>
	<p>W. on N. Bdy. of Secs. 4.</p> <p style="text-align: right;">Var. 20°30'E.</p>
22.00	Old wagon road, brs. N.W. & S.E.
40.00	<p>Set post, 4 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which</p> <p>A pine, 12 ins. diam., brs. N.57°W., 56 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A tamarack, 34 ins. diam., brs. S.30°E., 11 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>
47.30	Dry gulch, course N.W.
55.50	Spring branch, 2 lks. wide, runs N.20°W.
80.00	<p>Set basalt stone, 15 x 12 x 7 ins., 12 ins. in ground, for Cor. to Secs. 4, 5, 32 & 33, marked with 4 notches on E. and 2 notches on W. edges, from which</p> <p>A pine, 14 ins. diam., brs. N.49°E., 82 lks. dist., marked T.4 S., R.34 E., S.33, B.T.</p> <p>A pine, 8 ins. diam., brs. N.68°W., 175 lks. dist., marked T.4 S., R.34 E., S.32, B.T.</p> <p>A pine, 42 ins. diam., brs. S.43°W., 57 lks. dist., marked T.5 S., R.34 E., S.5, B.T.</p> <p>A pine, 49 ins. diam., brs. S.28°E., 167 lks. dist., marked T.5 S., R.34 E., S.4, B.T.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir & tamarack.</p> <p>Dense undergrowth of pine & fir.</p>