

. 1.

Exterior Bdys., T 5 N., R. 28 E., W M.
 As surveyed by Timothy W. Davenport, U.S. Deputy Surveyor,
 Under Contract No. 101,
 Dated Aug. 5th, 1861.

Chains	<p>Commencing at the post, the established Cor. to Tps. 5 N., Rs. 27 & 28 E., on the 1st Standard Parallel N.</p> <p>Thence</p> <p>N. bet. Secs. 31 & 36.</p> <p style="text-align: right;">Var. 21° E.</p>
40.00	Set $\frac{1}{4}$ Sec. post, made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 30, 31, 25 & 36; made mound and drove charred stake, as per instructions.
	<p>Surface nearly flat.</p> <p>Soil; sandy & gravelly.</p> <p>Sage, scattering, grass good.</p>
	<p>N. bet. Secs. 25 & 30.</p> <p style="text-align: right;">Var. 21° E.</p>
15.00	Commence to descend, table land.
20.00	Foot of table.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and deposited charred stake, as per instructions.
59.00	Remarkable sand ridge, 1.00 broad and 12 ft. high and brs. S. 65° W.
80.00	Set post Cor. to Secs. 19, 30, 24 & 25; made mound and deposited charred stake.
	Sunday, Sept. 15, 1861.
	<p>N. bet. Secs. 19 & 24.</p> <p style="text-align: right;">Var. 21° E.</p>
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 18, 19, 13 & 24; made mound and drove charred stake, as per instructions.
	<p>N. bet. Secs. 13 & 18.</p> <p style="text-align: right;">Var. 21° E.</p>
8.00	Commence to descend bluff.
17.00	Foot of bluff.