

Ext. Bdys., T. 5 N., R.27 E., W.M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake as per instructions.
44.00	Columbia Trail, course E. & W.
50.96	Set post, Meander Cor. to Secs. 13 & 18 on bank of Columbia River, 12 ft. above and 5.00 chs. dist from the water made mound and drove charred stake, as per instructions. Var.21°15'E.
<hr/> Subdivisional Lines & Meanders, T 5 N., R.27 E., W M. As surveyed by same U.S. Deputy Surveyor, Under same Contract & Date.	
<hr/> N. bet. Secs. 35 & 36. Var.21°E.	
28.00	Commence to descend.
35.00	Foot of table.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 25, 26, 35 & 36; made mound and drove charred stake, as per instructions.
<hr/> E. on random line bet. Secs. 25 & 36. Var.21°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.04	Intersect E. Bdy. of Tp., 21 lks. N. of Cor. to Secs. 25 & 36. N.89°51' W. on true line bet. Secs. 25 & 36.
15.00	Commence to descend.
22.00	Bottom of table.
40.02	Set $\frac{1}{4}$ Sec. post; made mound, with charred stake, as per instructions.
80.04	To Cor. of Secs. 25, 26, 35 & 36.
<hr/> N. bet. Secs. 25 & 26. Var.21°E.	